



B O N O C O N S U L T I N G , I N C .

Excavation



Removal of existing sod and topsoil/fill mix down to solid clay for base of new field.



Grade stakes placed for sub-base grades.



Firm clay base proof-rolled and ready for stone placement.

Base Course & Drainage



Geotextile fabric placed over sub-base. Perimeter drains as well as diagonal flat drains remove storm water from the stone base.



Stormwater Detention Storage to be placed in pipes and stone under the surface of the field.



Proof-rolling of the stone base to ensure quality performance.

Track & Field Construction



The stone base of the track has been proof-rolled and is ready for asphalt.



Asphalt placement.



Letters, numbers, and lines being placed on the turf.

Final Product



Final touches still required, but almost complete.



Finished Product.



Game Night.